## NOTES: UNLESS OTHERWISE SPECIFIED

- 1. THE ENGINEER OF RECORD SHALL VERIFY THE ADEQUACY OF THE SUPPORTING STRUCTURE INCLUDING ACCESS FLOOR PANEL TO RESIST THE GRAVITY AND LATERAL LDAD FROM THE EQUIPMENT.
- 2. WHEN INSTALLING BRILLED-IN ANCHORS IN EXISTING NON-PRESTRESSED REINFORCED CONCRETE. USE CARE AND CAUTION TO AVOID CUTTING OR DAMAGING THE EXISTING REINFORCING BARS. WHEN INSTALLING THEM INTO EXISTING PRESTRESSED CONCRETE (PRE- OR PDST-TENSIONED), LOCATE THE PRESTRESSED TENDONS BY USING A NON-DESTRUCTIVE METHOD PRIDR TO INSTALLATION. EXERCISE EXTREME CARE AND CAUTION TO AVOID CUTTING OR DAMAGING THE TENDONS DURING INSTALLATION. MAINTAIN A MINIMUM CLEARANCE OF ONE INCH BETWEEN THE REINFORCEMENT AND THE DRILLED-IN AMACHING
- ANCHDRAGE DESIGNED PER CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 2, 1998 EDITION, USING TABLE 168-D. Fp=Z \(\text{C}\)D \(\text{Vp}\), WHERE Z=.4 I=1.5 Coh=1.0 \(\text{Cov}=.33\).
- 4. TEST STANDARD: BELLCORE TECHNICAL REFERENCE TR-EOP-000063 ISSUE 3, MARCH 1988, SECTION 4.5.
- 5. ASSUMPTIONS: THE CONCRETE THAT THE "HDI" IS TO BE SET IN SHALL BE 3000 PSI (110 P.C.F. MINIMUM). STRUCTURAL ANGLE OR PLATE SHALL BE ASTM A-36 MINIMUM.
- 6. AGENCY CRITICAL PARTS. NO SUBSTITUTIONS OF MATERIALS ALLOWED.
- 7. TEST ANCHORS AS FOLLOWS:

TEST VALUES						
HARDROCK OR LIGHTWEIGHT CONCRETE						
ANCHOR DIA.	WEDGE LOAD TORQUE		SLEEVE LOAD TORQUE		SHELL LOAD TORQUE	
(IN)	(LBZ)	(FT-LBS)	(LBS)	(FT-LBS)	(LBS)	(FT-LBS)
1/4	000	10	400		1000	
	800	10	400	4	1000	-
5/16	-	_	400	5	1400	-
3/8	1100	25	700	10	1800	-
1/2	2000	50	900	20	2700	-
5/8	2300	80	1100	45	3700	-
3/4	3700	150	1400	90	5400	-
1	5800	250	-	-	-	-

- Q. SHELL TYPE ANCHORS SHOULD BE TESTED AS FOLLOWS:
  VISUALLY INSPECT 25%. FOR FULL EXPANSION AS EVIDENCED BY THE LOCATION OF
  THE EXPANSION PLUG IN THE ANCHOR BODY. PLUG LIGCATION OF A FULLY EXPANDED
  ANCHOR SHOULD BE AS RECOMMENDED BY THE MANUFACTURER, OR, IN THE ABSENCE
  OF SUCH RECOMMENDATION, AS DETERMINED ON THE JOB SITE FOLLOWING THE
  MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND, PROOF LIDAD 5%. AS INDICATED
  IN THE TABLE ABOVE, BUT NOT LESS THAN THREE ANCHORS PER DAY FOR EACH
  DIFFERENT PERSON OR CREW INSTALLING ANCHORS, OR, TEST 50% OF THE INSTALLED
  ANCHORS PER 1925B3.5.
- 6. TEST EQUIPMENT IS TO BE CALIBRATED BY AN APPROVED TESTING LABORATORY IN ACCORDANCE WITH STANDARD RECOGNIZED PROCEDURES.
- c. THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS: HYDRAULIC RAM METHOD: THE ANCHOR SHOULD HAVE NO DBSERVABLE MOVEMENT AT THE APPLICABLE TEST LOAD, FOR WEDGE AND SLEEVE TYPE ANCHORS, A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER UNDER THE NUT BECOMES LODSE.

TORQUE WRENCH METHOD: THE APPLICABLE TEST TORQUE MUST BE REACHED WITHIN THE FOLLOWING LIMITS:

WEDGE OR SLEEVE TYPE: DNE-HALF (1/2) TURN OF THE NUT.
DNE-QUARTER (1/4) TURN OF THE NUT FOR
THE 3/8 IN. SLEEVE ANCHOR DNLY.

- d, TESTING SHOULD DCCUR 24 HOURS MINIMUM AFTER INSTALLATION OF THE SUBJECT ANCHORS.
- e. IF ANY ANCHOR FAILS TESTING, TEST ALL ANCHORS OF THE SAME CATEGORY NOT PREVIOUSLY TESTED UNTIL TWENTY (20) CONSECUTIVE PASS, THEN RESUME THE INITAL TESTING FREQUENCY.

