



Powering Business Worldwide

Eaton UPS Full Capacitor Field Update Scope of Work Attachment R-35

Pre-Inspection and Safety Compliance

Inspection of the electronic portion of the Eaton® UPS, or “Power Module” shall be performed as needed during the contracted period of maintenance at no extra charge to Purchaser. Remedial maintenance provided by Contractor shall be excluded from this service. Pre-inspection and safety compliance inspection includes:

- Inspection of UPS for suitability and compliance of intended upgrade procedure
- Functional testing of all transfer conditions
- Inspection of online performance and equipment history
- Examination of interfaces to other Powertrain equipment

AC and/or DC Capacitor Update Installation

The UPS will be placed in bypass mode to enable installation of the capacitor update; installation of the update can be completed in a single day and will be performed by an Eaton field technician. The upgrade includes:

- Replacement of all applicable capacitors (Note: not all capacitors are recommended for replacement)
- Cleaning and adjustment of all replaced parts as necessary
- System testing
- Updating of system to reflect new capacitors
- Updating of customer’s spare parts inventory (if applicable)
- Provide confirmation to customer of upgrade completion, and answer questions

Eaton is a trademark of Eaton Corporation.